

CANREB status




P0310

Friedhelm Ames


ARIEL town hall meeting, January 11, 2017

Accelerating Science for Canada
Un accélérateur de la démarche scientifique canadienne

Owned and operated as a joint venture by a consortium of Canadian universities via a contribution through the National Research Council Canada
Propriété d'un consortium d'universités canadiennes, géré en co-entreprise à partir d'une contribution administrée par le Conseil national de recherches Canada



CANREB overview




main components of CANREB

- high resolution mass separator
 $M/\Delta M = 20,000$ for beams from ISAC and ARIEL
- charge state breeder A/q 5 - 7
 - RFQ cooler/buncher
 - EBIS charge state breeder
 - Nier spectrometer for highly charged ions
 - pulsed operation at 100 Hz



HRS requirements

- mass range up to $A = 238$
- beam energy 60 keV
- resolving power 20000 (no energy spread 3 μm emittance)
10000 (6 μm emittance)
- stable operation over extended time (weeks)
- fast set-up
- low intensity beam diagnostics

HRS - design




multipole corrector



Schematic of HRS Layout


HRS – dipole status

- Design aspects of the ARIEL-II HRS Dipole Magnet included in TRI-DN14-06 and TRI-DN-15-28
- Final external design review February 27, 2015
- procurement document for manufacturing signed, delivery 2017
- First dipole steel manufacturing completed, second dipole to be completed by the end of January
- Steel manufacturing inspection by TRIUMF to occur in the second half of January
- procurement for vacuum chamber signed, manufacturing started




OPERA model of
HRS Dipole Magnet

HRS – dipole status



pole on top of yoke




field clamps





coil winding and wrapping

charge breeding system



main pulse sequence









- gas filled radio frequency quadrupole (1-3 MHz)
- capturing of singly charged ions at 60 keV
- accumulating section
- release as ion bunches
- pulsed drift tube for energy matching to accelerator

external design review June 14, 2016

- detailed design nearly finished
- manufacturing of parts started
- prototype testing for pulsed drift tube done

RFQ buncher

detailed design for RFQ structure



RFQ electrodes parts

- Design drawings for RFQ structure, surrounding optics released to shop
- Differential pumping and RFQ electrode parts are being manufactured




pulsed drift tube

prototype test set up



pulsed drift tube (PDT) test results


- Desired voltages, rise time reached – PDT design concept validated
- Results will inform improved enclosure design to reduce discharge



EBIS requirements


- **beam acceptance**
 - singly charged ions
 - 10^6 ions per bunch
 - E 10 -14 keV
 - transversal emittance $5 \mu\text{m}$
 - bunch length $1 \mu\text{s}$
- **charge state breeding**
 - A/Q 5 -7,
 - 10-20% in the desired charge state
 - 100 Hz repetition rate
- **highly charged ion beam properties**
 - E 10 - 14 keV x Q
 - $\delta E \leq 100 \text{ eV} \times Q$
 - transversal emittance $\leq 20 \mu\text{m}$
 - bunch length up to 1 ms
- **background ions**
 - minimize contaminations
 - ultra high vacuum 5×10^{-12} mbar in trapping region

EBIS design




EBIS design specifications

- magnet
 - superconducting 6 T
 - $dB/B < 10^{-4}$
- electron beam
 - $I_{\max} = 550$ mA
 - electron beam density in trap region 20 000 A/cm²
 - effective density (seen by ions) 1300 A/cm²
 - beam diameter in trap region 60 μ m



charge state breeding for various elements
simulation with DITHER


EBIS setup



EBIS superconducting magnet

The superconducting magnet arrived in Heidelberg in May.







It was damaged during a quench in June and send back to the manufacturer.



The magnet arrived back in Heidelberg in October. It was thoroughly tested (several induced quenches) and is working fine.




To prevent future damages the steel rods supporting the magnet were made with a larger diameter, among other repairs.

EBIS trap electrodes assembly




EBIS electron gun

Electron gun is in assembly, some small parts need to be altered by the workshop



EBIS electron collector




collector assembly ready for installation





The magnetic coils for electron gun and collector needed to be wound and glued manually

- Superconducting magnet repaired, redelivered, installed and thoroughly tested-works
- Last components are produced and altered in the MPIK workshop
- Trap electrodes are installed inside magnet
- Collector and e-gun are nearly finished, will be installed in the next days/week
- Lab infrastructure (cooling water supply, pressurized air, ...) have been installed
- Ongoing simulations on injection/extraction/charge breeding

Nier spectrometer and beam lines





Nier spectrometer optics simulation



beam envelop for $^{133}\text{Cs}^{19+}$ @266 keV
($A/Q = 7 @ 2 \text{ keV/A}$)


phase space at mass slit
 $\delta E = \pm 0.25\%$, $\delta M = \pm 0.5\%$

Nier spectrometer magnet



magnet assembly and testing at manufacturer
delivery to TRIUMF in February 2017

Nier spectrometer and beam lines



Nier spectrometer optics

- optics lay out for Nier spectrometer done
- will use standard ARIEL RIB beam transport elements
- electrostatic elements in front of EBIS to be switched
- matching of RFQ beam to pulsed drift tube and EBIS to be finalized

CANREB schedule

HRS	<ul style="list-style-type: none">• magnet delivery to TRIUMF• magnet tested (field mapping)• Installation finished	April 2017 January 2018 June 2018
RFQ	<ul style="list-style-type: none">• parts ready for installation• installation finished	May 2017 April 2018
EBIS	<ul style="list-style-type: none">• shipment to TRIUMF• installation finished	September 2017 May 2017
Nier spectr beam lines	<ul style="list-style-type: none">• magnet delivery to TRIUMF• installation finished	February 2017 June 2018
Commissioning	<ul style="list-style-type: none">• with stable beam (CFI deliverable)• with beam from ISAC	July to October 2018 2019

Thank you!

Merci

F.A., Rick Baartman, Carla Barquest, Brad Barquest, Michael Blessenohl,
George Clark, Jose Crespo, Jens Dilling, Stepan Dobrodoj,
Leigh Graham, Renate Hubele, Rituparna Kanungo, Reiner Kruecken,
Jim Maloney, Marco Marchetto, Norman Muller, Matt Pearson,
Mike Rowe, Suresh Saminathan, Brad Schultz, David Wager

+ TRIUMF service groups

TRIUMF: Alberta | British Columbia |
Calgary | Carleton | Guelph | Manitoba |
McGill | McMaster | Montréal | Northern
British Columbia | Queen's | Regina |
Saint Mary's | Simon Fraser | Toronto |
Victoria | Western | Winnipeg | York

